



TOWN OF PITTSFORD

Building Department

DEMOLITION PERMIT INFORMATION

- Date of demolition
- Contractor Information including Liability, Workers Compensation and Disability Insurance.
- Determination of Asbestos: If asbestos is present then an abatement plan is needed.
- After abatement a survey must be completed to verify that all asbestos has been removed.
- Demolition plan: How will the house be demolished?
- What site safety will be provided?
- Is the structure on sewer? If so then the Sewer department must be notified. How will sewer lines be demolished and capped.
- If the structure is on septic a plan to reuse or decommission the tank(s) is required.
- Information as to the disposition of the material is required.
- Will the hole be filled? Where is the fill coming from?